

PRODUCT LEAFLET

Electric Vehicle Infrastructure Terra DC Wallbox UL



Future-proof "Destination DC" charging

The Terra DC Wallbox is a compact 24 kW DC fast charger with one or two outlets supporting CCS and CHAdeMO protocols.

Operating the Terra DC Wallbox is easy thanks to a full color, daylight readable touchscreen display. This includes starting and stopping of charge sessions, progress indication during charging, help menus, language selection, and PIN code access control.

As connectivity is the key to successful EV charging installations, the Terra DC Wallbox features ABB Ability Connected Services to enable authentication, payment, monitoring, remote diagnostics and repair, as well as over-the-air updates and upgrades.

Applications

- Commercial, retail parking
- Automotive dealers
- Right-of-way parking
- Office, workplace, campus
- Delivery fleets
- High voltage battery EV fleets
- Sites with sensitive load concerns

The UL certified Terra DC Wallbox is a compact 24 kW DC fast charger perfect for commercial parking, auto dealerships, workplace facilities and fleets.

With its low-power, high-voltage architecture, the Terra DC Wallbox can be installed at sites with defined or limited available power service – while offering 920 VDC charging capability for every EV model.

Benefits of low power DC solutions

Low power DC is an ideal solution for use cases demanding shorter charging times and higher charging asset utilization than can be provided by AC charging solutions. With a 24 kW compact DC solution, charging needs can be met in balance with load demands and infrastructure costs.

In AC charging solutions, the EV's onboard converter is usually the limiting factor on the charging power that can be supplied to the car. With typical onboard ratings ranging from 3 kW to 11 kW, any additional power the AC charger could provide is left unused. With the Terra DC Wallbox, 24 kW peak DC power is provided directly to the battery, bypassing the limitations of an EV's onboard converter.

High voltage charging capabilities

As electric vehicles and their use cases grow, high voltage DC charging has become more important to increase charging power while ensuring the highest safety, usability and utilization from charging assets. The Terra DC Wallbox can meet EV battery capabilities up to 920 VDC to enhance power output across a wider range of today's and tomorrow's EVs, including both passenger and fleet vehicles.

Main features

- Future-proof DC output voltage range from 150 to 920 VDC supporting EVs today and in the future
- Enables CCS1 only or CCS1 and CHAdeMO
- Daylight readable 7" full color touchscreen display
- Future proof connectivity:
 - OCPP 1.6 and Smart Charging Profiles
 - Capability for remote services and updates
- Compact design
- Robust all-weather enclosure for indoor and outdoor use
- RFID reader

Key optional features

- On-screen PIN code authorization
- Input current limiting software to match site requirements
- Web tools for statistics, configuration, access management, remote diagnostics and repair
- Integration with back offices and payment platforms
- Customized branding possibilities
- Pedestal mounted option available

Configurations

The Terra DC Wallbox is available in the following configurations:

- Single outlet CCS1
- Dual outlet CCS1 + CHAdeMO
- Single-phase, 208-240 VAC
- Three-phase, 480 VAC





Specifications

Electrical			
AC Input voltage range	(1) 208-240 VAC +/- 10% (60 Hz) (2) 480Y / 277 VAC +/- 10% (60 Hz)		
AC input power connection	(1) 1-phase: L1, L2, GND <mark>(2) 3-phase: L1, L2, L3, N, GND</mark>		
AC input current* and max power	(1) 100 A; 20.8-24 kVA (2) 32 A; 26.6 kVA 35 A; 26.6 kVA at 432 VAC (-10% dip) Current limiting options available		
Recommended upstream circuit breaker	(1) 125 A <mark>(2) 50 A</mark>		
Power Factor*	>0.96		
Current THD*	IEEE 519 Compliant; 5%		
DC output power	(1) 19.5 kW at 208 V (1) 22.5 kW at 240 V <mark>(2) 24 kW peak; 22.5 kW continuou</mark> s		
DC output voltage	<mark>CCS1: 150 - 920 VDC</mark> CHAdeMO: 150 - 500 VDC		
DC output current	60 A		
Efficiency*	94%		
Interface and Control			
Charging protocols	CCS1 and CHAdeMO		
User interface	7" full color touchscreen display		
RFID system	ISO/IEC14443A/B, ISO/IEC15693, NFC reader mode, Mifare, Calypso		
Network connection	GSM / <mark>4G modem</mark> 10/100 Base-T Ethernet		
Communication	OCPP 1.6 Core and Smart Charging Profiles; Autocharge via OCPP		
Support languages	English (others available on request)		
Environment			
Operating temperature	-35 °C to +45 °C (+45 °C to +55 °C with linear derating)		
Recommended storage conditions	-10 °C to +70 °C / 14 °F to +158 °C (dry environment)		
Protection	IP54, NEMA 3S; indoor and outdoor		
Humidity	5% to 95%, non-condensing		
Altitude	2500 m (8200 ft)		
General			
Charge cable	7 m (23 ft)		
Dimensions (H x W x D)	770 x 584 x 300 mm / 30.3 x 23 x 11.8 in		
Weight	<mark>60kg</mark> / 132 lbs excluding backplate (10 kg / 22 lbs) and cables		
Compliance and safety	UL 2202, CSA No. 107.1-16, NEC Article 625, EN 61851, EN 62196; CHAdeMO 1.2; DIN 70121, ISO 15118; IEC 61000-6-3, (2) EMC Class B		

(1) Single phase configuration

(2) Three phase configuration

* Data shown at nominal output power

ABB E-mobility Inc.

950 W Elliott Road, Suite 101 Tempe, AZ 85284 United States Phone: 800-435-7365 E-mail: US-evci@abb.com

e-mobility.abb.com

ABB E-mobility Inc.

800 Hymus Boulevard Saint-Laurent, QC H4S 0B5 Canada Phone: 800-435-7365 E-mail: CA-evci@abb.com We reserve the right to make technical changes or modify the contents of this document without prior notice. We reserve all rights in this document and in the subject matter and illustrations contained therein. Any reproduction, disclosure to third parties or utilization of its contents – in whole or in parts – is forbidden without prior written consent of ABB. Copyright© 2022 ABB. All rights reserved.



MANUAL: NORTH AMERICA

Terra DC Wallbox Single-phase Version Installation Manual

Revision 2.6





Revision level	Change	Date
2.1	Added revision level to document and added revision table	4-15-2021
2.2	Added ferrite information and changes pictures	10-22-2021
2.3	Added GID for optional gun holster – different connector type	03-16-2022
2.4	Added GID for minimal gun holster spare codes	03-31-2022
2.5	Added instructions to mounting gun holster	05-04-2022
2.6	Energy Star logo on the cover page	05-05-2023
2.7	Par. 5.4.1 note about number of people required to lift the DCWB	06-20-2023

Notice

This document contains information about one or more ABB products and may include a description of or a reference to one or more standards that may be generally relevant to the ABB products. The presence of any such description of a standard or reference to a standard is not a representation that all of the ABB products referenced in this document support all of the features of the described or referenced standard. In order to determine the specific features supported by a particular ABB product, the reader should consult the product specifications for the particular ABB product.

ABB may have one or more patents or pending patent applications protecting the intellectual property in the ABB products described in this document.

The information in this document is subject to change without notice and should not be construed as a commitment by ABB. ABB assumes no responsibility for any errors that may appear in this document. In no event shall ABB be liable for direct, indirect, special, incidental or consequential damages of any nature or kind arising from the use of this document, nor shall ABB be liable for direct, indirect, special, incidental or consequential damages of any nature or kind arising from the use of this document.

ing from the use of this document, nor shall ABB be liable for incidental or consequential damages arising from use of any software or hardware described in this document.

This document and parts thereof must not be reproduced or copied without written permission from ABB, and the contents thereof must not be imparted to a third party nor used for any unauthorized purpose.

Copyrights

All rights to copyrights, registered trademarks, and trademarks reside with their respective owners. Copyright © 2018 ABB. All rights reserved.



Contents

1	Intro	duction		6			
	1.1	Preface		6			
	1.2	Intende	6				
	1.3	Terra DO	C Wallbox hardware ordering details	6			
	1.4	Signs					
		1.4.1	Owner responsibilities	8			
		1.4.2	Tilting and handling	8			
		1.4.3	Sharp edges	9			
		1.4.4	Electric hazards	9			
		1.4.5	Installation safety	9			
	1.5	Environ	ment and disposal of waste	9			
2	Descr	Description of the product					
	2.1	Overview of the system					
		2.1.1	Complete overview				
		2.1.2	External view				
		2.1.3	Inside view	12			
3	Inctal	lation Dla	anning and Design	12			
5	3.1		t connection				
	5.1	3.1.1	Internet via cellular connection				
		3.1.2	Internet via ethernet connection				
	3.2	•	al requirements				
	0.2	3.2.1	Required electrical grid configuration				
		3.2.2	Overcurrent protection device				
		3.2.3	Conduit for power input wires				
		3.2.4	Specification for power input wires				
		3.2.5	Conduit for ethernet cable				
		3.2.6	Specification for ethernet cable				
	3.3	DC Wallbox placement					
		3.3.1	Charging cable reach				
		3.3.2	DC Wallbox position with respect to parking space				
		3.3.3	Required space for installing and maintaining the DC Wallbox				
		3.3.4	Ventilation and airflow required for the DC Wallbox				
		3.3.5	Considerations for where to position DC Wallbox vertically				
4	Instal	Installation instructions					
-	4.1						
	4.2						
		4.2.1	Mounting on a pedestal				
	4.3		eed				
	4.4						
5	Poco						
5	5.1	Acceiving, Placing and connecting					
	5.2		ing the charging and mounting preparations				
	5.2	5.2.1	Unpacking				
		5.2.2	Mounting preparations				
	5.3	-	abinet to position				
	-			==			



		5.3.1	Options	23
	5.4	Mounting	the Terra DC Wallbox	23
		5.4.1	Mounting the Terra DC Wallbox	
		5.4.2	Install cable gland(s) or connect conduit to the unit.	
	5.5	Connect cables		29
		5.5.1	Connect PE of power cable	29
		5.5.2	Connect power cable	29
	5.6	Instruction for Mounting the DC Wallbox Gun Holders		
		5.6.1	General	
		5.6.2	General description	
		5.6.3	Mounting instructions	31
6	Comm	nissioning .		
-	6.1	-	oning preparation	
7	Maintenance and Cleaning of the cabinet			
	7.1	Recomme	nded Periodic maintenance	34
	7.2	Cleaning	of the cabinet	34
8	Technical Data			
	8.1	Electrical data		
	8.2	Mechanic	al data	
	8.3	Environm	ent	
	8.4 Certifications			
9	9 Contact information			
10 Appendix A – Mounting points				
	10.1		Nallbox Charger wall mounting	
11	Apper	ndix B - Dis	posal instruction	
	11.1	Directive	on Waste Electrical and Electronic Equipment (WEEE – 2012/19/EU)	
12	Apper	ndix C – Pe	destal requirements	40



Glossary

AC Alternating Current.

CCS

Combined Charging System. This is the name of the charging protocol of European and North American car makers.

CHAdeMO DC fast charging method for electric vehicles.

Contractor

Entity hired by the owner / site operator to do engineering, civil and electrical installation work.

DC

Direct Current.

EV Electric Vehicle.

Grid provider Company responsible for the transportation and distribution of electricity.

HMI

Human Machine Interface; the display/screen on the charger.

NOC

ABB Network Operating Centre; remotely checks the correct functioning of the charger.

Owner The legal owner of the charger.

OCPP Open Charge Point Protocol. Open standard for communication with charge stations.

PE Protective Earth.

PPE

Personal Protective Equipment. Equipment such as safety shoes, helmet, glasses, gloves.

RCD Residual Current Device. Breaks the connection if a residual current is detected.

RFID

Radio-Frequency IDentification. RFID is a communication technology by means of radio waves to transfer data over a very short distance between a reader and an electronic tag or card.

Site operator

This entity is responsible for the day to day control of the charger. The site operator can be the owner, but not necessarily.

User

The owner of an electric vehicle, who uses the Charge Station to charge that vehicle.





1 Introduction

1.1 Preface

This guide provides an overview for the installation of the Terra DC Wallbox.

The Terra DC Wallbox charging station is an easy to install DC fast charger for electric vehicles. Fast chargers are electrical installations with high electric currents. Therefore, the installation must be planned carefully, and must be done by certified personnel only (according to local standards). Local regulations shall take precedence if they list different installation requirements than prescribed in this Installation Manual.

The Terra DC Wallbox is offered in a variety of configurations and with multiple connector types. The different versions are described in section 1.3.

Before installing the Terra DC Wallbox, read this installation guide carefully and attentively. Be sure to follow all instructions when installing the charger. ABB is not responsible for any damage caused by not following or incorrectly executing the instructions described in this manual.

1.2 Intended document users

This document is intended to be used by:

- Customers who have purchased a Terra DC Wallbox or customers in the process of ordering and require additional details on installation.
- Contractors who are responsible for site preparation and/or installation of a Terra DC Wallbox.

1.3 Terra DC Wallbox hardware ordering details

ABB's Terra DC Wallbox single-phase is offered in the following configurations:

- Terra DC Wallbox C UL
- Terra DC Wallbox J UL
- Terra DC Wallbox CJ UL
- C CCS-1 (Combo) standard
- J CHAdeMO standard

ABB6AGC107059

CJ CCS-1 (Combo) standard and CHAdeMO standard

All variations are offered with charging cable lengths up to 7 meters (23 ft). The Terra DC Wallbox comes with the standard connector holsters as shown.

Charging cable type	ABB order code (**)
CCS-1	ABB6AGC076604
CCS-1 (*)	ABB6AGC109619
CHAdeMO	ABB6AGC102972

^(**) the codes are referred to the spare parts. Minimal gun holster is included in the packaging

TWB UL 24 C 3M-7M-0-0

(*) CCS-1 minimal holster to be use in combination with products: ABB6AGC107060 TWB UL 24 C 7M-7M-0-0



ABB6AGC107314	TWB UL 24 CJ 7M-7M-0-0		
ABB6AGC109857	TWB UL 24 CJ 3M-7M-0-0		

Optional connector holsters shown below may be purchased separately with the order code details shown below.



Charging cable type	ABB order code
CCS-1	ABB6AGC076604
CCS-1 (*)	ABB6AGC109619
CHAdeMO	ABB6AGC076601

(*) CCS-1 optional holster to be use in combination with products:

ABB6AGC107060	TWB UL 24 C 7M-7M-0-0
ABB6AGC107059	TWB UL 24 C 3M-7M-0-0
ABB6AGC107314	TWB UL 24 CJ 7M-7M-0-0
ABB6AGC109857	TWB UL 24 CJ 3M-7M-0-0

1.4 Signs

The following signs are used on the equipment and in this manual:



DANGER

Hazardous voltage Identifies a hazard that could result in severe injury or death through electrocution.



WARNING Various Identifies a hazard that could result in severe injury or death.



WARNING Rotating parts Identifies a hazard that could result in injury due to the presence of rotating or moving parts.



Pinch Hazard Identifies a hazard that could result in injuries, in which some body parts are pinched or crushed.



CAUTION Various Identifies a hazard that could result in damage to the machine, other equipment, and/or environmental pollution.



CAUTION Environmental damage

WARNING

Identifies a hazard that could result in environmental damage and/or environmental pollution.

NOTICE Contains remarks, suggestions or advice.

1.4.1 **Owner responsibilities**

The owner and site operator are required to:

- Operate the charge station with the protective devices installed and to ensure all protective devices are correctly installed after carrying out installation or maintenance work.
- Write an emergency plan that instructs people what to do in case of emergency.
- Prepare the site where the charge station will be installed according to the requirements described in this guide.
- Ensure there is sufficient space around the charger to carry out maintenance work.
- Appoint a person responsible for the safe operation of the charge station and for the coordination of all work.

The owner is cautioned that changes or modifications not expressly approved by ABB could void the owner's authority to operate the equipment and ABB's warranty policy.

Neither ABB nor its affiliates shall be liable to the purchaser of this product or third parties for damages, losses, costs or expenses incurred by purchaser or third parties as a result of: an accident, misuse or abuse of this product or unauthorized modifications, repairs or alterations to this product, or failure to strictly comply with ABB's operating and maintenance instructions.

1.4.2 Tilting and handling



WARNING Heavy equipment The Terra DC Wallbox weighs approximately 70 kg. Follow the handling Instructions: 1. Two people are recommended for the installation and wall-mounting of a Terra DC Wallbox.

2. Do not drop the Terra DC Wallbox.

1.4.3 Sharp edges



WARNING

Sharp metal edges

There could be sharp metal edges inside the Terra DC Wallbox. It is recommended to wear mash protecting gloves when working inside the charger.

1.4.4 Electric hazards



DANGER Hazardous voltage

The Terra DC Wallbox contains conductors under hazardous electrical voltages. The grid terminals on the internal DIN rail may carry hazardous voltages, even if all circuit breakers are switched off.

1.4.5 Installation safety



DANGER Hazardous voltage Instructions:

1. Always switch off the input circuit feeding the unit, (external disconnect or breaker) before performing any installation, disassembly, repair or replacement of components. Follow appropriate requirements for safe work practices, including but not limited to NFPA-70e.

2. Perform a voltage check to ensure electrical power is disconnected from the system.

 Only ABB certified technicians should commission the Terra DC Wallbox.
 When the system is in an open or dangerous condition, do not allow unqualified persons to go near it. Instruct and warn people about the potentially harmful high voltages.

5. The installation and maintenance personnel must supply their own lighting equipment because the Terra DC Wallbox has no lights inside the cabinet.

6. Always connect the Protective Earth (PE) first, before connecting the other power input wires.

7. Be sure to properly and securely reassemble the Terra DC Wallbox's enclosure after installation or service operations.

8. When handling the equipment, a proper lifting device should be used in accordance with your local EHS policies.

1.5 Environment and disposal of waste




NOTICE

Always follow the local rules and regulations regarding disposal of any (non-reusable) Terra DC Wallbox parts.

2 Description of the product

2.1 Overview of the system


2.1.1 Complete overview



Example of a complete installation

- A Power distribution board of the owner
- B Cables in conduit
- C Terra DC Wallbox
- D Parking space for charging
- E Electric vehicle

2.1.2 External view



- A Display / HMI
- B RFID card reader
- C DC Charging cable
- D Air outlet

- Emergency stop button
- AC input connection point for Conduit
- Air inlet

Е

F

G

Н

L

- Optional Holster (purchased separately)
- Standard Holster (included)




Standard charging cable holster supplied with DC wallbox



Optional charging cable holster sold separate from DC wallbox





- A AC input board
- B CPI and IMI boards
- C External Fan (2x)

D Cable gland for DC output(2x) E Cable gland for AC input

3 Installation Planning and Design

This section provides several considerations for the DC Wallbox installation planning and design, which are to be made by the customer to ensure a successful project.

3.1 Internet connection

ABB requires an internet connection to the DC Wallbox to conduct remote service operations including, oversight of the product during the warranty period, diagnosis and troubleshooting of issues, and performing software firmware update. Not having internet connection to the DC Wallbox may severely impact, or even void, the product warranty and/or ABB's service level agreement (SLA).

It is the installer's responsibility to ensure reliable internet connection to the DC Wallbox is made. Contingency planning and the associated costs are the responsibility of the installer.

3.1.1 Internet via cellular connection

The preferred method of establishing internet connection to the charger is using the charger's standard featured hardware with ABB's Charger Connect service offering, which provides internet access via Vodafone's 4G LTE wireless network.

In the USA, Vodafone primarily roams on the AT&T and T-Mobile 4G LTE networks. It is expected that a cellular availability test is performed prior to construction to ensure there is reasonable signal quality to at least one of the AT&T and T-Mobile 4G LTE bands 2 (1900 MHz), 4 (1700/2100MHz), or 12 (700 MHz).

The signal strength must be greater than -85dbm and should be measured with a cellular network signal meter, such as a Squid-4G or Sure Call device. Handheld mobile phones are not recommended for assessing signal strength since they are not reliable measuring devices.

The DC Wallbox only supports SIM cards provided by ABB. Customer procured SIM cards are not supported.

3.1.2 Internet via ethernet connection

Internet connection to the charger may be performed by connecting an ethernet cable to the charger from other on-site IT infrastructure. However, due to the scope of work required for integrating this solution to ensure secure communication, this method is typically not preferred.

ABB may require additional commissioning fees if ethernet cable method for establishing internet is used, depending on the situation. Please contact your ABB sales representative for more details.

See sections 3.2.5 and 3.2.6 for more details on connection of conduit carrying ethernet cable and specification of the ethernet cable.

3.2 Electrical requirements




CAUTION


The installation company is responsible to design and install the electrical installation according to the local regulations.

3.2.1 Required electrical grid configuration

Is essential that the DC Wallbox 1-phase input variant is installed in the proper electrical grid configuration. The allowable grid configurations are shown in the figures below. Please observe the 1-phase variant DC Wallbox supports two different grid configurations. For the 1-phase variant DC Wallbox, ABB recommends the electrical designer to consider power distribution phase balancing design requirements.



One of two electrical grid configurations acceptable for use with 1-phase, DC Wallbox UL variant (1ø, 208V input)



One of two electrical grid configurations acceptable for use with 1-phase, DC Wallbox UL variant (1ø, 240V input)

NOTICE:

The grid connections shown for the various configurations of the DC Wallbox are mandatory. Failure to adhere to these instructions may partially or fully void the product warranty, result in a costly site visit to reconfigure the grid configuration, and/or cause several site visits for the DC Wallbox commissioning. ABB is not responsible for scheduling delays and additional costs from not properly planning the installation. If ABB is contracted to perform the DC Wallbox commissioning, ABB observes the right to charge additional money for more than one site visit required for the commissioning due to an initial, improper installation of the DC Wallbox.

Important steps to ensure project success include:

1. Identify the grid configuration at the location where the DC Wallbox will be installed. If the grid configuration available is not okay for use with the DC Wallbox, then determine how to establish the required grid connection. A transformer solution offered by ABB is available to derive the required grid configuration when the required grid configuration is not available. Contact your local ABB sales representative for more details.

2. Select the 1-phase variant of the DC Wallbox according to Section 1.3 titled Terra DC Wallbox hardware ordering details based on Step 1 above.

3. Carefully execute a project plan to ensure the correct variant of DC Wallbox is used on the project and that the project site's grid configuration is compatible with the DC Wallbox.

4. Verify the actual grid configuration the DC Wallbox is installed in matches the described criteria during the DC Wallbox commissioning.

3.2.2 Overcurrent protection device

Both variant of the DC Wallbox is recommended to be fed by the circuit breaker or fuse ratings shown below.

• 1-phase, 208-240V DC Wallbox variant: 2-pole, 125A circuit breaker or fuses

3.2.3 Conduit for power input wires

Both variant of the DC Wallbox supports up to a 1-1/4'' trade size conduit connection.

3.2.4 Specification for power input wires

The exact size and type of wires used must be defined by the customer and be protected by customer provided overcurrent protection according to local codes and regulations.

The input terminals for 1-phase UL variant of the DC Wallbox accept a range of wire sizes from 10 AWG to 0 AWG. Wire terminals are rated 75C.

The 1-phase UL variant DC Wallbox requires Two (2) phase wires and One (1) wire for protective earth. (2W+G)

All wires 1-phase variant of the DC Wallbox may connect directly to the ABB provided terminals.

The integrity of the electrical grounding is essential. Ensure that the equipment grounding terminal is used in the device and an actual grounding conductor is installed to provide a path back to the source upstream panel. (Do not use the conduit or raceway as the sole equipment grounding conductor).

3.2.5 Conduit for ethernet cable

The DC Wallbox does not have a hole designated for a conduit carrying only an ethernet cable to connect to. If ethernet cable solution is required for an installation, please contact your ABB sales contact person to review ethernet cable entry solutions.

3.2.6 Specification for ethernet cable

If the cellular connection is not available, ethernet connection must be made to the charger using a shielded 8P+PE ethernet cable with RJ45 connectors. Additional recommendations include:

- Maintain distance of 75 meters or less. Distances over 75 meters require a custom engineered solution.
- Minimum bandwidth: upload: 128 kb/s download: 4 Mb/s
- 99.9% availability
- 600V rated cable that may route beside input power wires for short distances


3.3 DC Wallbox placement

Placement of the Terra DC Wallbox must be carefully determined by accounting for charging cable reach, DC Wallbox position with respect to parking space, bollards and wheel stops, ventilation and working clearances, and other local codes and regulations (e.g. ADA requirements in the USA).

3.3.1 Charging cable reach


The Terra DC Wallbox charging cables are available in lengths of 3.5 or 7 meters. The charging cables exit the charger enclosure on both the right and left sides. The cables and the connectors mounted on the cables are different depending on the charging standard and vary in flexibility.

The figure below shows an example of a dual connector charger with both types of connector and the corresponding reach area. The green circle with a continuous line describes the CHAdeMO cable 3.5m and the red circle with a continuous line describes the CCS cable 3.5m. The broken lines indicate the same cable types with a length of 7 meters (23 ft).




3.3.2 DC Wallbox position with respect to parking space

The charging inlets on a vehicle can be located at different positions depending on the manufacturer. The most common vehicles have inlets located either on the front or in the back on either the left or right side.



This makes some charger placements with respect to the parking space more favorable than others. Keep this in mind when designing a site. Below are examples of possible situations:



3.3.3 Required space for installing and maintaining the DC Wallbox


The Terra DC Wallbox requires a minimum space of 36" x 48". This space is calculated as follows:

- Charger size (H x W x D): 30.3 x 23 x 11.8 in

- Bottom side 23.6" (15.75" from the Terra DC Wallbox in order to avoid obstacles for the electrical connection).


- Left and right side 300mm/12", in order to operate without obstacles on the lateral side of the Terra DC Wallbox.

Note: The below dimensions are shown in millimeters.




3.3.4 Ventilation and airflow required for the DC Wallbox

The Terra DC Wallbox has an air inlet on the bottom side and an outlet on the top side.



3.3.5 Considerations for where to position DC Wallbox vertically

The below picture shows the height of the operable parts and display screen from the top and bottom of the DC Wallbox' s enclosure (not accounting for piece on enclosure where the customer conduits connect to). It is the installer's responsibility to use this information to define the height at which to install the DC Wallbox from the ground and to ensure compliance to local codes and regulations (e.g. ADA requirements in the USA).



4 Installation instructions

4.1 About construction

The construction phase includes all work required to prepare the location and ensure it is ready for the placement and connection of the Terra DC Wallbox charger. The construction phase can start when:

- The wall preparation work is done.
- All necessary permits are granted.
- The grid connection is available.

4.2 Instruction for a wall bearing

- 1. Drill and tap 4 holes and insert the plug for fixation in the wall at the indicated positions (refer to technical drawing in the Appendix A par. 10.1). For safety purposes, the number of recommended fixing screws is 4xST7.3x70. This is assuming the appropriate type of wall plugs are used (depends on wall's characteristics, structure and type). It is the installer's responsibility to choose an appropriate wall plug and to plan for a load of 820 N on each plug.
- 2. When selecting the area along the wall for installation, ensure the required free spaces for the Terra DC Wallbox cables are available (refer to section 3.4).

4.2.1 Mounting on a pedestal

The Terra DC Wallbox can also be mounted on a pedestal. In order to achieve a safe installation, the minimum set of requirements are included in Appendix C – Pedestal requirements). For the ABB pedestal solution, contact your local ABB sales representative.

4.3 Power feed

The power cable enters the charger from below. Use conduit, foam, or proper cable lugs and glands to prevent animals from entering the AC or Ethernet cable inlets. (Reference Section 3.2 for feeder specifications)

4.4 Internet connection

The preferred method of communication is the wireless 4G modem integrated into the charger. A customer SIM card is not required. A subscription for the SIM card is provided by ABB for select countries.

If there is no wireless signal available, a standard wired internet connection is required. (Reference Section 3.1, 3.2.5 and 3.2.6 for wiring and connection methods)

- The connection must be available for the ABB service engineer and the NOC (Network Operation Center).
- Please contact ABB (800.825.2556 option 2) for a specific configuration.

If a separate internet connection is not used, please ensure the cable entry hole is closed to retain the IP54 grade of the cabinet and prevent insects and small animals from entering the cabinet.

5 Receiving, Placing and connecting

5.1 Receiving the Wallbox

The product is delivered by a transport company to a warehouse where it will be handed over.

Transporting the Terra DC Wallbox to its final location (last mile service) is not included standard in the order.




NOTICE

The delivery truck unloads the pallet carrying the Terra DC Wallbox. The movement of the Terra DC Wallbox to its final location is the responsibility of the customer / contractor.

Ensure the Terra DC Wallbox has not been shaken or tilted.

• The cabinet is equipped with Shock Watch and Tilt Watch indicators.





Checking the Shock Watch and Tilt Watch PLUS sensors:


If the Shock Watch indicator is red, or the Tilt Watch PLUS indicator is tilted over 30°:

- 1. Do not refuse the delivery / receipt.
- 2. Make a notation on the delivery receipt and inspect cabinet for damage.
- 3. If damage is discovered, leave cabinet in original package and request immediate inspection from carrier within 3 days of delivery.
- 4. Contact your local ABB office.

5.2 Unpacking the charging and mounting preparations

5.2.1 Unpacking

The packaging of the Terra DC Wallbox can be removed without the use of tools. Follow local regulations on disposal of packaging material.



- 1. Remove the plastic protection profiles.
- 2. Remove the bottom air grate grill and the lower frontal cover.
- 3. Remove the wall frame.
- 4. Remove the Terra DC Wallbox. (USE CAUTION TO NOT DAMAGE THE E-STOP BUTTON ON THE SIDE OF THE ENCLOSURE)
- 5. Remove the AC ferrite core link to the outlet gun cable (assembly position shown at paragraph 5.4.2)
- 6. For all components above, remove the shrink wrap.

5.2.2 Mounting preparations

Unpack the IP BOX and verify all the following items are present:

- Wall frame
- Frontal cover
- Bottom grid cover

5.3 Move cabinet to position

5.3.1 Options

A properly rated lifting devices should be used to move the Terra DC Wallbox from the delivery truck to the installation location.



DANGER Hazardous voltage Ensure the product's power supply group main switch is set to the OFF position. Perform a voltage check to verify there is no electrical power on the cables or on the system. Secure the product from resetting.



NOTICE Warranty Damage due to moving the cabinet to its position is not considered a warranty issue.

5.4 Mounting the Terra DC Wallbox

Preconditions:

- Tools: Spanner/Wrench size 17.
- Guide the power cable through the central cable gland, and the Ethernet cable if required, through the smaller gland. Install the power wiring in the conduit/raceway that is connected to the unit. See below image for a typical conduit install make ready for installation of the Wallbox.




5.4.1 Mounting the Terra DC Wallbox




NOTICE

The minimum number of people required to lift and install the Terra DC Wallbox must be determined based on the relevant local regulation with taking into account the maximum allowed weight per person as well as the usage of the appropriate and suitable lifting equipment. The definition of the exact lifting equipment and working method for lifting is the responsibility of the installation contractor.

- 1. Carefully lower the Terra DC Wallbox onto its location.
- 2. Ensure cable(s) are not entrapped.
- 3. Place the wall frame in the correct position on the wall bearing by aligning the four holes of the charger with the corresponding holes on the wall bearing.
- 4. Tighten the four screws with stainless steel 8.8 hexagonal bolts.




5. Place the unit on the wall frame by correctly aligning the 6 bolts (3 for each lateral side).




6. Tighten the two M5 bolts on the lower side of the unit. Pay attention to the internal fan power supply cable. CAUTION: DO NOT SET SMALL OBJECTS ON TOP MESH COVER, ITEMS MAY FALL INTO THE COOLING FINS OR FAN COMPONENTS.






M5 Bolts (2x)


- 7. Let the auxiliary power supply cable pass through the central gland and tighten it.
- 8. IMPORTANT, connect both of the cooling fans to their power connections before proceeding to close the covers. There are two connectors one for the left fan and one for the right fan.



9. AFTER the completing wiring terminations, take the bottom cover grill and put it on the lower side of the unit and fix it by tightening two screws as shown in the following picture. Please note the 3-phase and 1-phase versions have a slightly different bottom grill assembly




10. Take the lower frontal cover and place it on the lower side of the unit. Secure it in place by tightening the two screws.



SWIPE THE LOWER FRONTAL COVER

11. Center the holes on the plastic cover with the pins on the box.



12. Place the central cover on the unit and secure it in place by tightening the two screws located on the left and right side of the cover. Center the bottom pins, rotate the cover, and tighten the 2 lateral screws.




5.4.2 Install cable gland(s) or connect conduit to the unit.

The maximum diameter of the grid cable is 32 mm. The opening is pre-punched for a 1.25" trade size conduit. The minimum diameter of the grid cable is 22 mm with the standard fitted cable gland insert.




Conduit Install shown as a comparison

1. Slide the cable inside the grommets, ensure at least 10mm of cable external jacket inside the box (see notes at the end of this section, before sliding the cable inside the grommet. Allow at least 24 inches of wire from the conduit entry point to allow enough wire to route thru the internal grommet/cable glands and wrap around to the terminal blocks.



2. Push the cables back through the gland plate, until sufficient cable length is left to reach the cable terminals. Ensure the PE cable is longer than the other cables.



1-Phase Connection using flexible




Conduit Installation 1.25" secured to bottom mounting area. 1-phase Version Shown

3. Slide the cable cover and tighten the two screws.

If a wired internet connection is not used, please ensure the cable entry hole is closed, to assure the IP54 grade of the cabinet, and prevent insects and small animals to enter the cabinet.

NOTE 1: For 3-phase versions a ferrite core is provided with the Wallbox (plastic bag within the package or strapped to the CCS-1 cable) and needs to be installed in commissioning phase. The Ferrite needs to be inserted in the AC in cable and located in the screw cable cover (see picture above, left). *THE FERRITE IS REQUIRED TO MAINTAIN THE WARRANTY*.

NOTE 2: Two floating grounding cables are provided that are connected to the ground node. One cable must be connected between the to the wall frame PEM the other to the front lower cover in order to guarantee equal ground potential (see picture above, right).



5.5 Connect cables

5.5.1 Connect PE of power cable

Preconditions:

• Tools: Wire stripper pliers; wire-end lug pliers; wire-end lug.

DANGER



Hazardous voltage Make sure that the main switch of the power supply group for the product is set to the OFF position. Perform a voltage check and make sure that the electrical power is disconnected from the system. Follow recommended *NFPA-70e* procedures.

1. Cut the PE wire of the power cable to the correct length (equal than the other phases) to reach the PE connector.



NOTICE

For safety, it is recommended that the PE wire is longer than the phase wires. This ensures the PE wire will be the last wire connected if the Terra DC Wallbox is moved by a collision.

- 2. Use wire stripper pliers to remove 0.75 in (20 mm) of the insulation from the end of the PE wire and attach the cable lugs.
- 3. Pull the cover away from the connectors and remove them.
- 4. Loosen the bolts of the PE connector
- 5. Attach the PE wire on the PE connector as indicated on the label on the relative terminal block
- 6. Tighten the bolts. The advised torque value is 2.9 Nm.

5.5.2 Connect power cable

Preconditions:

Tools: Wire stripper pliers; wire-end lug pliers; wire-end lugs.


DANGER



Hazardous voltage Ensure the product's power supply group's main switch is set to the OFF position. Perform a voltage check and ensure the electrical power is disconnected from the system.

- 7. Cut the 2 phase wires of the power cable to the correct lengths to reach the connectors.
- 8. Use wire stripper pliers to remove 0.75 in (20 mm) of the insulation from the ends of the wires insert and attach the cable lugs
- 9. Pull the covers away from the connectors and remove them.
- 10. Loosen the bolts of the connectors.
- 11. Attach the 2 wires on to their connectors as indicated on the label on the relative terminal block (see the following picture as example).

From left to right for the 1-phase unit (as showed in the following picture):
 PE- terminal block green/yellow, L2 - terminal block grey, L1 - terminal block grey



- 12. Tighten the bolts. The advised torque value is 2.9Nm.
- 13. After terminating the wires, make sure to adjust the terminal blocks so they are properly aligned as misalignment can occur while applying proper torque to the connectors (as shown in 208/240V terminal layout above)

5.6 Instruction for Mounting the DC Wallbox Gun Holders

5.6.1 General

This document is intended to provide an instruction for service team / installers in order to be able to properly install the terra DC wallbox gun holders.

5.6.2 General description

The Terra DC wallbox is provided with two types of gun holders. A standard gun holder is provided with all the DC wallboxes. The standard Terra DC wallbox gun holder is illustrated in Fig.1 and 2**Error! Reference source not found.** An optional gun holder is also available a s an optional / spare part and can be ordered as external kit. The optional gun holder is illustrated in Fig. 3 and 4. All the above described gun holders include adapters for CCS or Chademo charging guns.

5.6.3 Mounting instructions

The gun holders described above are intended for a very simple installation. Standard gun holder is provided with 3 holes for wall hooking while optional one is provided with a wall mounted hooking bar (10 in Fig.3) to be mounted to wall. The recommended dowels to be used are of 10 size for both cases.





Figure 3: Terra DC wallbox optional gun holder.

Figure 4: Terra DC wallbox optional Gun holder; front and side view.



2) Fix the system on the bracket (XAP.V2M09.0)

3) Fix Screw on hole number 3

6 Commissioning

6.1 Commissioning preparation

Commissioning is the last phase necessary to get the Terra DC Wallbox operational. The purpose is to check the safe functioning of the charger for its operational purpose.

A certified service engineer from the ABB Service department or a trained engineer by ABB is required to perform the commissioning. During this commissioning, the safety and the functioning of the charger will be tested. ABB Form Titled "**SI-TWBCE-001 UL CSAT Procedure DC Wallbox**", (Charger System Acceptance Test) should be used for the commissioning process as it contains the checklist and contact information for activation of the charger warranty.

Before the service engineer can start, the following conditions must be met:

- All work described in Preparation, Construction and Placement and connection is complete with Power available.
- A local technician is present for assistance and to switch on the power.
- Internet access must be available in case 4G is not functional.
- A Combo compliant electric vehicle must be available for testing CCS charging.
- A CHAdeMO compliant electric vehicle must be available for testing the CHAdeMO charging.
- Any electric vehicle for instructing the site operator.



NOTICE

Warranty : It is not allowed to move the Terra DC Wallbox, after it is commissioned. In case the Terra DC Wallbox is moved without approval from ABB, the warranty will be considered void. In case of relocation please contact the local ABB Service department.

Commissioning is executed according to the CSAT checklist, this check list can be found in the Helios Suite Service tool that is available to the certified commissioning engineers or their supervising ABB organization. The following data is required for input:

- End-user Contact person (Create a contact if it doesn't exist).
- Charger address (Check the site address, it will be the address the charger was shipped to).
- Coordinates longitude and latitude for plots on the maps. If there are more chargers on 1 location, make sure the coordinates are slightly different (at least 0,0001 degrees) to prevent being displayed on the same location.
- Site name if this is useful for better recognition (example: Shell petrol station Amsterdam).
- External fuse of the charger.
- SAT (Site Acceptance Test) date.

Location remarks (any special remarks about the site, e.g. behind a gate, no photo cameras allowed etc.). Add a picture of the surrounding of the charger, upload the local CAF document A4 on the page of the charger in PDF. Change Deliver status to <SAT>.

After completing the Site Acceptance Test, ABB's Network Operation Center will be triggered to perform a final check on the connection and configuration of the charger.

Upon approval the charger will be operational and initialized for use.

7 Maintenance and Cleaning of the cabinet

7.1 Recommended Periodic maintenance

- A. Following *NFPA-70e* procedures, de-energize unit, open cover, inspect air filter, clean or replace as needed.
- B. Check input connections and terminations for proper toque values
- C. Check Grounding resistance
- D. Exercise input breaker and output DC breakers
- E. Open HMI cover, inspect capacitors and fuse connections.
- F. Clean interior with a HEPA vacuum.
- G. Blow out rear cooling fins and remove any debris
- H. Reassemble unit, energize verify input voltage, perform a charging session.
- I. Using the connected network verify charging session details.

7.2 Cleaning of the cabinet

The Terra DC Wallbox Charger is powder coated. This coating must be kept in good condition.

Clean the Terra DC Wallbox Charger three times a year in the following way:

- Remove rough dirt by spraying with low-pressure tap water.
- Apply a neutral or weak alkaline cleaning solution and let it soak.
- Remove dirt by hand with a non-woven nylon hand pad.
- Rinse thoroughly with tap water.
- Do a check on the coating and on the front cover for damage.



NOTICE

When the Terra DC Wallbox Charger is exposed to rain, it is sufficient to clean it twice a year.



CAUTION

Do not apply high-pressure water jets. Water may leak into the Terra DC Wallbox Charger. If a high-pressure water jet has been used, ensure the inside of the Terra DC Wallbox Charger is dry.

- Only use cleaning agents with a pH value between 6 and 8.
- Do not use cleaning agents with abrasive components.
- Do not use abrasive tools.

8 Technical Data

8.1 Electrical data

AC Input	
AC input voltage range	208 - 240 V _{AC} +/- 10% (60Hz)
AC input power connection	1-phase, 208-240 V _{AC} : L1, L2, GND
Maximum rated input current at nominal voltage	100 A
Recommended upstream overcurrent protection device rating	125 A
Power factor	> 0.96
Efficiency	94% at nominal output power
DC output	
Maximum DC output power	19.5 kW @ 208 V 22.5 kW @240 V
DC output voltage range	CCS1: 150 - 920 VDC CHAdeMO: 150 - 500 VDC
Maximum DC output current	60 ADC

(1) Single phase configuration

General	
DC connection standard	EN61851-23 / DIN 70121 CCS 2 CHAdeMO 1.0
DC cable length	3.5 meters or 7 meters (12 feet or 23 feet)
DC plug type	CCS 1 / CHAdeMO
RFID data	ISO/IEC14443A/B, ISO/IEC15693, NFC reader mode, Mifare, Calypso
RFID system	FeliCa™1, NFC reader mode
Network connection	GSM / 4G modem 10/100 Base-T Ethernet

8.2 Mechanical data

Mechanical data	
Dimensions (H x W x D)	770 mm x 585 mm x 300 mm / 30.32" x 23.03" x 11.81"
Weight	70 kg / 154.32lbs
Volume	0,135 m3
Dimensions including packaging (H X W x D)	650 mm x 1200 mm x 800 mm /25.6" x 47.25" x 31.5"
Weight including packaging	80 kg / 176.37 lbs.
Mechanical impact protection	IK10

8.3 Environment

Environmental data	
Ingression protection	IP54, NEMA 3S; indoor and outdoor
Temperature range – Operation	-35°C to + 55°C /-31F to + 131F
	(derating applies between 45°C and 55°C / 113F-131F)
Temperature range - Storage	-40 °C to +70 °C / -40F to +158F
Humidity	20% - 95% RH - non-condensing
Operational noise level	55 dBA @25°C
Altitude	2500 m max.

8.4 Certifications

EMC: EN 61000-6-4 Class A emission; EN 61000-6-3 Class B emission; EN 61000-6-2 immunity.

LVD: IEC 61851-23, IEC 61851-1, IEC 62196

RFID: ETSI EN 300 330

- UL 2202
- CSA STD C22.2 No. 107.1
- FCC Part 15 Class A

9 Contact information



NOTICE

In case of problems Please contact your local ABB Service organization or Service partner for first line problem analysis and solving. In case they cannot solve the problem, they will contact the second line Service organization.

ABB in your country

Please contact ABB in your country for sales, delivery and service information.

ABB EV Infrastructure USA

ABB Inc. 950 E Elliott Rd Tempe, AZ 85284 Suite 100 United States Phone: 800-435-7365 E-mail: US-evci@us.abb.com

ABB EV Infrastructure Canada


ABB Inc. 800 Hymus Boulevard Saint-Laurent, QC H4S 0B5 Canada Phone: 800-435-7365 E-mail: CA-evci@abb.com

ABB EV Infrastructure Global

- Address Heertjeslaan 6 2629 JG, Delft The Netherlands
- Telephone +31 70 307 62 00
- Mail info.evi@nl.abb.com

10 Appendix A – Mounting points

10.1 Terra DC Wallbox Charger wall mounting



Appendix B - Disposal instruction 11

Directive on Waste Electrical and Electronic Equipment (WEEE -11.1 2012/19/EU)

X

X

Ø

podlegający ywą (WEEE

R

ABB ENGLISH

equipment (WEEE

oduct shall not be mixed or disp nold waste, at their end of use. all be handed over to your local com-ll doit être remis à un point de colle le recyclage des appareils électrique

X

X

X

Směrn.

zdravi

POLSKI Sprzęt Elek

wate handling cold possibly have a dangeresse field on the environment and human health sur l'environ in the correct disposal of this product, you horease, recycle and precision 4 to reuse, recycle and precision 4 to reuse and the precision 4 to reuse and the

FRANCAIS ents é aux déchets d'équipements électriques et iques (WEEE - 2012/19/EU) ole (poubelle interdite) apposé

Pour de plus amples informations, veuillez contacter le service de collecte des déchets ménagers local.

substances potent it avoir des effets ontient qui pe t et la santé hur correcte de ce p ine. En duit, vo ESPAÑOL Aparatos eléctri modo separado sobre residuos de aparat cos (WEEE - 2012/19/EU)

Los productos identificad pelera tachada) no deber eben eliminarse nalizada su vida Este producto debe entregarse a un pu

Para mayor info con el Departan su Ayuntamiento nto de Dispo Elm

NEDERLASNDS

X

X

SVENSKA

Elektrische en elekti afzonderlijk ingezamel van de Rich

symbool (doorg het product geeft aan dat het van haar levensduur niet same huishoudafval mag worden we

Het product moet naar depot) worden gebracht eem voor meer inf

Het kan nadelig

DANSK Elektrisk og el

Ø

Ø

SUOMI

ja ter voi aihe epäasia

oita en asia

SRPSKI

X

viia ko-

prügi-

udstyr (WEEE - 2012/1 trisk og elektror

X

X

ntakt ve

sig bortskaffelse af affald kan ha ing på miljøet og folks hell

DEUTSCH

ČESKY

Elektrická

MAGYAR

Elektro der Richtlinie über äte (WEEE - 2012/19/

telle abzugeben ist. ationen wenden Sie sich bitte an die

ständigen örtlichen Behörd mäßer Entsorgung besteht das Risiko uswirkungen auf Umwelt und Gesun-tentiell gefährliche Substanzen. Durch on zur ordnungsgemäßen Entsorgung in Windneuengemand des Recelling

je třeba odložit na

ní s odpady by mohlo mít za násle

ITALIANO

Per ul ento dei rifiuti inappropriato può avere vi sull'ambiente e sulla salute umana a anze potenzialmente pericolose. Collabo-

entos Eléc resíduos de equipar (WEEE - 2012/19/EU) olo (caixote de lixo de

PORTUGUÊS

Este produto deverá ser entr

O trata

ivo o

označuje, da se tega izdelka po ne sme mešati ali odvreči z jskimi odpadki.

Elektriska och VEEE - 2012

Pvvdä lisätietoia iä Tämän tuotteen stamisella auteta

Vi ber om ditt samar produkt för att bidra

olas elektri- ja o

X

Električna i EU)

na vašem pr

Ovaj proizvod se mora p otpada za reciklažu u va Za dodatne organ za odl

Nepravilno rukovanje otpadom može utiče na životnu sredinu i zdravlje ljudi, z no opasnih supetanci. Vršeno

X

X

rjük, forduljon az országában

Produkt ten powinien zostać dostar komunalnego punktu zbiórki odpad ami w Twoim kraju.

aściwe manipulowanie odpadami może nie tek otencjam Jjąc przy prawk ≏⊽vniasz się do ~⁴uktu i

SLOVENČINA

LIETUVIŲ

jūsų

macijos galite gauti akų tvarkymo departami as gali neigiamai veikti nes atliekose gali büti šalinim ~kata

ΕΛΛΗΝΙΚΆ

X

Täpse ma informatsiooni saamiseks pal iigiasutuse poole Teie riigis, mis oleva toote vale käsitlemine selle kõn põhjustada võimalikest riskiainetest iivset mõju nii keskkonnale kui ka Te ote korrektne käsitsemine ka peale s pri pr X

X

ira ločeno ktrični in

končani ostalimi

EESTI

Elektri

a prügiga

Käesolev toode on ümbe halikku prügikogumis- võ

Ta izdelek je potrebno oddati vaši lokalni deponiji z odpadki za predelavo takšnih izdelkov.

obnejše podatke se obmite na državni urad za jevanje odpadkov v vaši državi. Za po Zaradi nevarnih snovi ima lahko napačno upravljanje z

SLOVENŠČINA

Električna in elektronska v skladu z Direktivo

odpa zdra odst adki negativn avje ljudi. Z

LATVIEŠU

šalies

12 Appendix C – Pedestal requirements

Any pedestal solution designed for Terra DC Wallbox needs to fulfill the specific ISO standards for civil constructions (note: specific local regulations may apply).

Additionally, whereas no specific constraint is provided by local regulations, the minimum set of requirements necessary to provide a safe installation are listed in the table below to be verified in the temperature range between -50° C - $+60^{\circ}$ C:

Minimum Wind load resistance	100km/h
Minimum compression load capability (applied on center of mass of the WB)	4kN
Side / Back / frontal impact MAX (applied on the pedestal/WB) higher point	3kN
Pulling /Pushing force applied (to gun holders if they are mechanically con- nected to same structure and external to the WB area)	3kN
Min / Max distance of gun holder from WB (if mechanically connected to pedestal structure)	300mm / 1000mm
Rust protection paint	Yes
Minimum clearance areas side / top / bottom around the charger	300mm
Recommended foundation requirements (min tilting torque)	To be designed consid- ering the max loads in each direction
Vibration test required on the full system	According to procedure described in IEC 60068- 2-27: 2008 and IEC 60068-2-6: 2007
Electrical ground connection	To the chassis of the DCWB



INSTALLATION MANUAL NORTH AMERICA

Terra DC Wallbox North America Three-phase Version

Revision 2.9





Revision level	Change	Date
2.1	Added revision level to document and added revision table	04-15-2021
2.2	Added bulletin to make sure L1,L2,L3,N,PE are all connected prior to powering up	08-05-2021
2.3	Added new gun holder standard pictures	10-22-2021
2.4	Changed new DC Wallbox figures	10-22-2021
2.5	Added GID for optional gun holster – different connector type	03-16-2022
2.6	Added GID for minimal gun holster spare codes	03-31-2022
2.7	Added instruction to mounting gun holster	04-05-2022
2.8	Changed AC circuit breaker and Input current values	10-20-2022
2.9	Energy Star logo on the cover page	05-05-2023
3.0	Par. 5.4.1 note about number of people required to lift the DCWB	06-20-2023

Notice

This document contains information about one or more ABB products and may include a description of or a reference to one or more standards that may be generally relevant to the ABB products. The presence of any such description of a standard or reference to a standard is not a representation that all of the ABB products referenced in this document support all of the features of the described or referenced standard. In order to determine the specific features supported by a particular ABB product, the reader should consult the product specifications for the particular ABB product.

ABB may have one or more patents or pending patent applications protecting the intellectual property in the ABB products described in this document.

The information in this document is subject to change without notice and should not be construed as a commitment by ABB. ABB assumes no responsibility for any errors that may appear in this document. In no event shall ABB be liable for direct, indirect, special, incidental or consequential damages of any nature or kind arising from the use of this document, nor shall ABB be liable for incidental or consequential damages arising from use of any software or hardware described in this document.

This document and parts thereof must not be reproduced or copied without written permission from ABB, and the contents thereof must not be imparted to a third party nor used for any unauthorized purpose.

Copyrights


All rights to copyrights, registered trademarks, and trademarks reside with their respective owners. Copyright © 2022 ABB.



All rights reserved.

ATTENTION:

YOU **MUST** CONNECT L1, L2, L3, N AND PE WIRES BEFORE POWERING UP THIS CHARGER. FAILURE TO DO SO WILL CAUSE DAMAGE TO THE CHARGER AND VOID WARRNTY L1, L2, L3, N AND PE LABELS ARE ON THE TERMINAL BLOCK





Scan QR Code to get the latest Installation Manual



Contents

1	Intro	duction		7	
	1.1	Preface		7	
	1.2 Intended document users			7	
	1.3 Terra DC Wallbox hardware ordering details				
	1.4	Signs	~	8	
		1.4.1 Owner	responsibilities	9	
		1.4.2 Tilting	and handling	9	
		1.4.3 Sharp	edges	9	
		1.4.4 Electri	c hazards	9	
		1.4.5 Install	ation safety	10	
	1.5	Environment an	d disposal of waste	10	
2	Desc	ription of the pr	oduct	11	
	2.1	Overview of the	system	11	
		2.1.1 Comp	ete overview	11	
		2.1.2 Extern	al view	12	
		2.1.3 Inside	view	13	
3	Insta	llation Planning	and Design	14	
	3.1	Internet connec	ion	14	
		3.1.1 Interne	et via cellular connection	14	
		3.1.2 Interne	et via ethernet connection	14	
	3.2		ements		
			ed electrical grid configuration		
		3.2.2 Overc	urrent protection device	16	
		3.2.3 Condu	it for power input wires	16	
		3.2.4 Specif	ication for power input wires	16	
			it for ethernet cable		
		3.2.6 Specif	ication for ethernet cable	17	
	3.3	DC Wallbox pla	cement	17	
		3.3.1 Charg	ing cable reach	17	
			allbox position with respect to parking space		
			ed space for installing and maintaining the DC Wallbox		
			tion and airflow required for the DC Wallbox		
		3.3.5 Consid	derations for where to position DC Wallbox vertically	20	
4	Insta	llation instruction	ons	20	
	4.1	About construct	on	20	
	4.2 Instruction for a wall bearing		Instruction for a	wall bearing	20
		4.2.1 Mount	ing on a pedestal	20	
	4.3				
	4.4	Internet connec	ion	21	
5	Rece	iving, Placing a	nd connecting	21	
	5.1 Receiving the Wallbox				
	5.2	Unpacking the o	harging and mounting preparations	22	
			king		
			ing preparations		
	5.3	Move cabinet to	position	23	



		5.3.1	Options	23
	5.4	Mounting	the Terra DC Wallbox	23
		5.4.1	Mounting the Terra DC Wallbox	
		5.4.2	Install cable gland(s) or connect conduit to the unit	27
	5.5	Connect	cables	
		5.5.1	Connect PE of power cable	
		5.5.2	Connect power cable	
	5.6		n for Mounting the DC Wallbox Gun Holders	
		5.6.1	General	
		5.6.2	General description	
		5.6.3	Mounting instructions	
6	Com	nissionin	g	
•	6.1		sioning preparation	
_				
7			nd Cleaning of the cabinet	
	7.1		ended Periodic maintenance	
	7.2	Cleaning	of the cabinet	
8	Techi	nical Data	1	
	8.1	Electrica	l data	
	8.2	Mechani	cal data	
	8.3	Environm	nent	
	8.4	Certificat	ions	
9	Cont	act inform	nation	
10			Mounting points	
	10.1	Terra DC	Wallbox Charger wall mounting	
11	Appe	ndix B - [Disposal instruction	
	11.1		on Waste Electrical and Electronic Equipment (WEEE – 2012/19/EU)	
12	Appe	ndix C –	Pedestal requirements	



Glossary

AC

Alternating Current.

ccs

Combined Charging System. This is the name of the charging protocol of European and North American car makers.

CHAdeMO

DC fast charging method for electric vehicles.

Contractor

Entity hired by the owner / site operator to do engineering, civil and electrical installation work.

DC

Direct Current.

EV Electric Vehicle.

Grid provider

Company responsible for the transportation and distribution of electricity.

HMI

Human Machine Interface; the display/screen on the charger.

NOC

ABB Network Operating Centre; remotely checks the correct functioning of the charger.

Owner

The legal owner of the charger.

OCPP

Open Charge Point Protocol. Open standard for communication with charge stations.

PE

Protective Earth.

PPE

Personal Protective Equipment. Equipment such as safety shoes, helmet, glasses, gloves.

RCD

Residual Current Device. Breaks the connection if a residual current is detected.

RFID

Radio-Frequency IDentification. RFID is a communication technology by means of radio waves to transfer data over a very short distance between a reader and an electronic tag or card.

Site operator

This entity is responsible for the day to day control of the charger. The site operator can be the owner, but not necessarily.

User

The owner of an electric vehicle, who uses the Charge Station to charge that vehicle.





1 Introduction

1.1 Preface

This guide provides an overview for the installation of the Terra DC Wallbox.

The Terra DC Wallbox charging station is an easy to install DC fast charger for electric vehicles. Fast chargers are electrical installations with high electric currents. Therefore, the installation must be planned carefully, and must be done by certified personnel only (according to local standards). Local regulations shall take precedence if they list different installation requirements than prescribed in this Installation Manual.

The Terra DC Wallbox is offered in a variety of configurations and with multiple connector types. The different versions are described in section 1.3.

Before installing the Terra DC Wallbox, read this installation guide carefully and attentively. Be sure to follow all instructions when installing the charger. ABB is not responsible for any damage caused by not following or incorrectly executing the instructions described in this manual.

1.2 Intended document users

This document is intended to be used by:

- Customers who have purchased a Terra DC Wallbox or customers in the process of ordering and require additional details on installation.
- Contractors who are responsible for site preparation and/or installation of a Terra DC Wallbox.
- •

1.3 Terra DC Wallbox hardware ordering details

ABB's Terra DC Wallbox single-phase is offered in the following configurations:

- Terra DC Wallbox C UL
- Terra DC Wallbox CJ UL

Where:

- C CCS-1 (Combo) standard
- J CHAdeMO standard
- CJ CCS-1 (Combo) standard and CHAdeMO standard

All variations are offered with charging cable lengths of 7 meters (23 ft). The Terra DC Wallbox comes with the standard connector holsters as shown.

The ferra DC wallbox comes with the standard connector holsters as	
Charging cable type	ABB order code ^(*)
CCS-1	ABB6AGC076604
CCS-1 ^(**)	ABB6AGC109619
CHAdeMO	ABB6AGC102972



^(*) the codes are referred to the spare parts. Minimal gun holster is included in the packaging

(**) CCS-1 minimal holster to be use in combination with products:

ABB6AGC107062	TWB UL 24 C 7TM-7M-0-0
ABB6AGC107061	TWB UL 24 C 3TM-7M-0-0
ABB6AGC107315	TWB UL 24 CJ 7TM-7M-0-0

Optional connector holsters shown below may be purchased separately with the order code details shown below.

Charging cable type	ABB order code
CCS-1	ABB6AGC076604
CCS-1 (*)	ABB6AGC109619
CHAdeMO	ABB6AGC076601



(*) CCS-1 optional holster to be use in combination with products:

\ / 	
ABB6AGC107062	TWB UL 24 C 7TM-7M-0-0
ABB6AGC107061	TWB UL 24 C 3TM-7M-0-0
ABB6AGC107315	TWB UL 24 CJ 7TM-7M-0-0



1.4 Signs

The following signs are used on the equipment and in this manual:

CAUTION Various



DANGER Hazardous voltage Identifies a hazard that could result in severe injury or death through electrocution.



WARNING Various Identifies a hazard that could result in severe injury or death.



WARNING Rotating parts Identifies a hazard that could result in injury due to the presence of rotating or moving parts.



WARNING Pinch Hazard Identifies a hazard that could result in injuries, in which some body parts are pinched or crushed.



CAUTION Environmental damage Identifies a hazard that could result in environmental damage and/or environmental pollution.

Identifies a hazard that could result in damage to the machine, other

equipment, and/or environmental pollution.





NOTICE Contains remarks, suggestions or advice.

1.4.1 Owner responsibilities

The owner and site operator are required to:

- Operate the charge station with the protective devices installed and to ensure all protective devices are correctly installed after carrying out installation or maintenance work.
 - Write an emergency plan that instructs people what to do in case of emergency.
- Prepare the site where the charge station will be installed according to the requirements described in this guide.
- Ensure there is sufficient space around the charger to carry out maintenance work.
- Appoint a person responsible for the safe operation of the charge station and for the coordination of all work.

The owner is cautioned that changes or modifications not expressly approved by ABB could void the owner's authority to operate the equipment and ABB's warranty policy.

Neither ABB nor its affiliates shall be liable to the purchaser of this product or third parties for damages, losses, costs or expenses incurred by purchaser or third parties as a result of: an accident, misuse or abuse of this product or unauthorized modifications, repairs or alterations to this product, or failure to strictly comply with ABB's operating and maintenance instructions.

1.4.2 Tilting and handling



WARNING
Heavy equipment
The Terra DC Wallbox weighs approximately 70 kg. Follow the handling Instructions:
1. Two people are recommended for the installation and wall-mounting of a Terra DC Wallbox.
2. Do not drop the Terra DC Wallbox.

1.4.3 Sharp edges



WARNING

Sharp metal edges There could be sharp metal edges inside the Terra DC Wallbox. It is recommended to wear mash protecting gloves when working inside the charger.

1.4.4 Electric hazards



DANGER

Hazardous voltage The Terra DC Wallbox contains conductors under hazardous electrical voltages. The grid terminals on the internal DIN rail may carry hazardous voltages, even if all circuit breakers are switched off.

1.4.5 Installation safety



DANGER

Hazardous voltage Instructions:

1. Always switch off the input circuit feeding the unit, (external disconnect or breaker) before performing any installation, disassembly, repair or replacement of components. Follow appropriate requirements for safe work practices, including but not limited to NFPA-70e.

2. Perform a voltage check to ensure electrical power is disconnected from the system.

3. Only ABB certified technicians should commission the Terra DC Wallbox.

4. When the system is in an open or dangerous condition, do not allow unqualified persons to go near it. Instruct and warn people about the potentially harmful high voltages.

5. The installation and maintenance personnel must supply their own lighting equipment because the Terra DC Wallbox has no lights inside the cabinet.

6. Always connect the Protective Earth (PE) first, before connecting the other power input wires.

7. Be sure to properly and securely reassemble the Terra DC Wallbox's enclosure after installation or service operations.

8. When handling the equipment, a proper lifting device should be used in accordance with your local EHS policies.

1.5 Environment and disposal of waste




NOTICE

Always follow the local rules and regulations regarding disposal of any (non-reusable) Terra DC Wallbox parts.

2 Description of the product

2.1 Overview of the system


2.1.1 Complete overview



Example of a complete installation

- A Power distribution board of the owner
- B Cables in conduit
- C Terra DC Wallbox
- D Parking space for charging
- E Electric vehicle

2.1.2 External view



- A Display / HMI
- B RFID card reader
- C DC Charging cable
- D Air outlet
- E

Н

I

- Emergency stop button
 - F AC input connection point for Conduit
 - G Air inlet
 - Optional Holster (purchased separately)
- Standard Holster (included)




Standard charging cable holster supplied with DC wallbox



Optional charging cable holster sold separate from DC wallbox





- A AC input board
- B CPI and IMI boards
- C External Fan (2x)

D Cable gland for DC output(2x) E Cable gland for AC input

3 Installation Planning and Design

This section provides several considerations for the DC Wallbox installation planning and design, which are to be made by the customer to ensure a successful project.

3.1 Internet connection

ABB requires an internet connection to the DC Wallbox to conduct remote service operations including, oversight of the product during the warranty period, diagnosis and troubleshooting of issues, and performing software firmware update. Not having internet connection to the DC Wallbox may severely impact, or even void, the product warranty and/or ABB's service level agreement (SLA).

It is the installer's responsibility to ensure reliable internet connection to the DC Wallbox is made. Contingency planning and the associated costs are the responsibility of the installer.

3.1.1 Internet via cellular connection

The preferred method of establishing internet connection to the charger is using the charger's standard featured hardware with ABB's Charger Connect service offering, which provides internet access via Vodafone's 4G LTE wireless network.

In the USA, Vodafone primarily roams on the AT&T and T-Mobile 4G LTE networks. It is expected that a cellular availability test is performed prior to construction to ensure there is reasonable signal quality to at least one of the AT&T and T-Mobile 4G LTE bands 2 (1900 MHz), 4 (1700/2100MHz), or 12 (700 MHz).

The signal strength must be greater than -85dbm and should be measured with a cellular network signal meter, such as a Squid-4G or Sure Call device. Handheld mobile phones are not recommended for assessing signal strength since they are not reliable measuring devices.

The DC Wallbox only supports SIM cards provided by ABB. Customer procured SIM cards are not supported.

3.1.2 Internet via ethernet connection

Internet connection to the charger may be performed by connecting an ethernet cable to the charger from other on-site IT infrastructure. However, due to the scope of work required for integrating this solution to ensure secure communication, this method is typically not preferred.

ABB may require additional commissioning fees if ethernet cable method for establishing internet is used, depending on the situation. Please contact your ABB sales representative for more details.

See sections 3.2.5 and 3.2.6 for more details on connection of conduit carrying ethernet cable and specification of the ethernet cable.


3.2 Electrical requirements



CAUTION The installation company is responsible to design and install the electrical installation according to the local regulations.

3.2.1 Required electrical grid configuration

It is essential that the DC Wallbox 3-phase input variant is installed in the proper electrical grid configuration. The allowable grid configuration is shown in the figure below.



Electrical grid configuration required for 3-phase, DC Wallbox UL variant (3ø, 480Y/277V input)

NOTICE:

The grid connections shown for the various configurations of the DC Wallbox are mandatory. Failure to adhere to these instructions may partially or fully void the product warranty, result in a costly site visit to reconfigure the grid configuration, and/or cause several site visits for the DC Wallbox commissioning. ABB is not responsible for scheduling delays and additional costs from not properly planning the installation. If ABB is contracted to perform the DC Wallbox commissioning, ABB observes the right to charge additional money for more than one site visit required for the commissioning due to an initial, improper installation of the DC Wallbox. Important steps to ensure project success include:

1. Identify the grid configuration at the location where the DC Wallbox will be installed. If the grid configuration available is not okay for use with the DC Wallbox, then determine how to establish the required grid connection. A transformer solution offered by ABB is available to derive the required grid configuration when the required grid configuration is not available. Contact your local ABB sales representative for more details.

2. Select the 1-phase or 3-phase variant of the DC Wallbox according to Section 1.3 titled Terra DC Wallbox hardware ordering details based on Step 1 above.

3. Carefully execute a project plan to ensure the correct variant of DC Wallbox is used on the project and that the project site's grid configuration is compatible with the DC Wallbox.

4. Verify the actual grid configuration the DC Wallbox is installed in matches the described criteria during the DC Wallbox commissioning.

3.2.2 Overcurrent protection device

Each variant of the DC Wallbox is recommended to be fed by the circuit breaker or fuse ratings shown below.

• 3-phase, 480Y/277V DC Wallbox variant: 3-pole, 50A circuit breaker or fuses

3.2.3 Conduit for power input wires

Each variant of the DC Wallbox supports up to a 1-1/4" trade size conduit connection.

3.2.4 Specification for power input wires

The exact size and type of wires used must be defined by the customer and be protected by customer provided overcurrent protection according to local codes and regulations.

The input terminals for 3-phase UL variants of the DC Wallbox accept a range of wire sizes from 10 AWG to 0 AWG. Wire terminals are rated 75C.

The 3-phase UL variant DC Wallbox requires Three (3) phase wires, One (1) neutral wire, and One (1) wire for protective earth. (3W+N+G)

All wires for 3-phase variants of the DC Wallbox may connect directly to the ABB provided terminals, with exception to the protective earth wire. The protective earth wire requires for the installer to crimp a terminal onto it using the terminal manufacturer's recommended crimp procedure and tool.

The integrity of the electrical grounding is essential. Ensure that the equipment grounding terminal is used in the device and an actual grounding conductor is installed to provide a path back to the source upstream panel. (Do not use the conduit or raceway as the sole equipment grounding conductor).

3.2.5 Conduit for ethernet cable

The DC Wallbox does not have a hole designated for a conduit carrying only an ethernet cable to connect to. If ethernet cable solution is required for an installation, please contact your ABB sales contact person to review ethernet cable entry solutions.

3.2.6 Specification for ethernet cable

If the cellular connection is not available, ethernet connection must be made to the charger using a shielded 8P+PE ethernet cable with RJ45 connectors. Additional recommendations include:

- Maintain distance of 75 meters or less. Distances over 75 meters require a custom engineered solution.
- Minimum bandwidth: upload: 128 kb/s download: 4 Mb/s
- 99.9% availability
- 600V rated cable that may route beside input power wires for short distances


3.3 DC Wallbox placement

Placement of the Terra DC Wallbox must be carefully determined by accounting for charging cable reach, DC Wallbox position with respect to parking space, bollards and wheel stops, ventilation and working clearances, and other local codes and regulations (e.g. ADA requirements in the USA).

3.3.1 Charging cable reach


The Terra DC Wallbox charging cables are available in lengths of 3.5 or 7 meters. The charging cables exit the charger enclosure on both the right and left sides. The cables and the connectors mounted on the cables are different depending on the charging standard and vary in flexibility.

The figure below shows an example of a dual connector charger with both types of connector and the corresponding reach area. The green circle with a continuous line describes the CHAdeMO cable 3.5m and the red circle with a continuous line describes the CCS cable 3.5m. The broken lines indicate the same cable types with a length of 7 meters (23 ft).




3.3.2 DC Wallbox position with respect to parking space


The charging inlets on a vehicle can be located at different positions depending on the manufacturer. The most common vehicles have inlets located either on the front or in the back on either the left or right side.




This makes some charger placements with respect to the parking space more favorable than others. Keep this in mind when designing a site. Below are examples of possible situations:




Lateral Backward parking



Backward parking



Lateral Forward parking



3.3.3 Required space for installing and maintaining the DC Wallbox


The Terra DC Wallbox requires a minimum space of 36" x 48". This space is calculated as follows:

- Charger size (H x W x D): 30.3 x 23 x 11.8 in

- Bottom side 23.6" (15.75" from the Terra DC Wallbox in order to avoid obstacles for the electrical connection).

- Left and right side 300mm/12", in order to operate without obstacles on the lateral side of the Terra DC Wallbox.

Note: The below dimensions are shown in millimeters.




3.3.4 Ventilation and airflow required for the DC Wallbox

The Terra DC Wallbox has an air inlet on the bottom side and an outlet on the top side.




NOTICE Free air flow If necessary, take precautions to prevent snow or objects from blocking the inlets and outlets.



3.3.5 Considerations for where to position DC Wallbox vertically

The below picture shows the height of the operable parts and display screen from the top and bottom of the DC Wallbox's enclosure (not accounting for piece on enclosure where the customer conduits connect to). It is the installer's responsibility to use this information to define the height at which to install the DC Wallbox from the ground and to ensure compliance to local codes and regulations (e.g. ADA requirements in the USA).



4 Installation instructions

4.1 About construction

The construction phase includes all work required to prepare the location and ensure it is ready for the placement and connection of the Terra DC Wallbox charger. The construction phase can start when:

- The wall preparation work is done.
- All necessary permits are granted.
- The grid connection is available.

4.2 Instruction for a wall bearing

- Drill and tap 4 holes and insert the plug for fixation in the wall at the indicated positions (refer to technical drawing in the Appendix A par. 10.1). For safety purposes, the number of recommended fixing screws is 4xST7.3x70. This is assuming the appropriate type of wall plugs are used (depends on wall's characteristics, structure and type). It is the installer's responsibility to choose an appropriate wall plug and to plan for a load of 820 N on each plug.
- 2. When selecting the area along the wall for installation, ensure the required free spaces for the Terra DC Wallbox cables are available (refer to section 3.4).

4.2.1 Mounting on a pedestal

The Terra DC Wallbox can also be mounted on a pedestal. In order to achieve a safe installation, the minimum set of requirements are included in Appendix C – Pedestal requirements). For the ABB pedestal solution, contact your local ABB sales representative.

4.3 Power feed

The power cable enters the charger from below. Use conduit, foam, or proper cable lugs and glands to prevent animals from entering the AC or Ethernet cable inlets. (Reference Section 3.2 for feeder specifications)

4.4 Internet connection

The preferred method of communication is the wireless 4G modem integrated into the charger. A customer SIM card is not required. A subscription for the SIM card is provided by ABB for select countries.

If there is no wireless signal available, a standard wired internet connection is required. (Reference Section 3.1, 3.2.5 and 3.2.6 for wiring and connection methods)

- The connection must be available for the ABB service engineer and the NOC (Network Operation Center).
- Please contact ABB (800.825.2556 option 2) for a specific configuration.

If a separate internet connection is not used, please ensure the cable entry hole is closed to retain the IP54 grade of the cabinet and prevent insects and small animals from entering the cabinet.

5 Receiving, Placing and connecting

5.1 Receiving the Wallbox

The product is delivered by a transport company to a warehouse where it will be handed over.

Transporting the Terra DC Wallbox to its final location (last mile service) is not included standard in the order.




NOTICE

The delivery truck unloads the pallet carrying the Terra DC Wallbox. The movement of the Terra DC Wallbox to its final location is the responsibility of the customer / contractor.

Ensure the Terra DC Wallbox has not been shaken or tilted.

• The cabinet is equipped with Shock Watch and Tilt Watch indicators.



Checking the Shock Watch and Tilt Watch PLUS sensors:


If the Shock Watch indicator is red, or the Tilt Watch PLUS indicator is tilted over 30°:

- 1. Do not refuse the delivery / receipt.
- 2. Make a notation on the delivery receipt and inspect cabinet for damage.
- 3. If damage is discovered, leave cabinet in original package and request immediate inspection from carrier within 3 days of delivery.
- 4. Contact your local ABB office.

5.2 Unpacking the charging and mounting preparations

5.2.1 Unpacking

The packaging of the Terra DC Wallbox can be removed without the use of tools. Follow local regulations on disposal of packaging material.



- 1. Remove the plastic protection profiles.
- 2. Remove the bottom air grate grill and the lower frontal cover.
- 3. Remove the wall frame.
- 4. Remove the Terra DC Wallbox. (USE CAUTION TO NOT DAMAGE THE E-STOP BUTTON ON THE SIDE OF THE ENCLOSURE)
- 5. Remove the AC ferrite core link to the outlet gun cable (assembly position shown at paragraph 5.4.2)
- 6. For all components above, remove the shrink wrap.

5.2.2 Mounting preparations

Unpack the IP BOX and verify all the following items are present:

- Wall frame
- Frontal cover
- Bottom grid cover

5.3 Move cabinet to position

5.3.1 Options

A properly rated lifting devices should be used to move the Terra DC Wallbox from the delivery truck to the installation location.



DANGER Hazardous voltage Ensure the product's power supply group main switch is set to the OFF position. Perform a voltage check to verify there is no electrical power on the cables or on the system. Secure the product from resetting.



NOTICE Warranty Damage due to moving the cabinet to its position is not considered a warranty issue.

5.4 Mounting the Terra DC Wallbox

Preconditions:

- Tools: Spanner/Wrench size 17.
- Guide the power cable through the central cable gland, and the Ethernet cable if required, through the smaller gland. Install the power wiring in the conduit/raceway that is connected to the unit. See below image for a typical conduit install make ready for installation of the Wallbox.




5.4.1 Mounting the Terra DC Wallbox




NOTICE

The minimum number of people required to lift and install the Terra DC Wallbox must be determined based on the relevant local regulation with taking into account the maximum allowed weight per person as well as the usage of the appropriate and suitable lifting equipment. The definition of the exact lifting equipment and working method for lifting is the responsibility of the installation contractor.

- 1. Carefully lower the Terra DC Wallbox onto its location.
- 2. Ensure cable(s) are not entrapped.
- 3. Place the wall frame in the correct position on the wall bearing by aligning the four holes of the charger with the corresponding holes on the wall bearing.
- 4. Tighten the four screws with stainless steel 8.8 hexagonal bolts.




5. Place the unit on the wall frame by correctly aligning the 6 bolts (3 for each lateral side).




 Tighten the two M5 bolts on the lower side of the unit. Pay attention to the internal fan power supply cable. CAUTION: DO NOT SET SMALL OBJECTS ON TOP MESH COVER, ITEMS MAY FALL INTO THE COOLING FINS OR FAN COMPONENTS.







- 7. Let the auxiliary power supply cable pass through the central gland and tighten it.
- 8. IMPORTANT, connect both of the cooling fans to their power connections before proceeding to close the covers. There are two connectors one for the left fan and one for the right fan.



9. AFTER the completing wiring terminations, take the bottom cover grill and put it on the lower side of the unit and fix it by tightening two screws as shown in the following picture. Please note the 3-phase and 1-phase versions have a slightly different bottom grill assembly




10. Take the lower frontal cover and place it on the lower side of the unit. Secure it in place by tightening the two screws.



SWIPE THE LOWER FRONTAL COVER

11.Center the holes on the plastic cover with the pins on the box.



12. Place the central cover on the unit and secure it in place by tightening the two screws located on the left and right side of the cover. Center the bottom pins, rotate the cover, and tighten the 2 lateral screws.




5.4.2 Install cable gland(s) or connect conduit to the unit.

The maximum diameter of the grid cable is 32 mm. The opening is pre-punched for a 1.25" trade size conduit. The minimum diameter of the grid cable is 22 mm with the standard fitted cable gland insert.



Conduit Install shown as a comparison


1. Slide the cable inside the grommets, ensure at least 10mm of cable external jacket inside the box (see notes at the end of this section, before sliding the cable inside the grommet. Allow at least 24 inches of wire from the conduit entry point to allow enough wire to route thru the internal grommet/cable glands and wrap around to the terminal blocks. (For the 3-phase version, remember to route the wires thru the ferrite)



NOTE 1: For 3-phase versions a ferrite core is provided with the Wallbox (plastic bag within the package or strapped to the CCS-1 cable) and needs to be installed in commissioning phase. The Ferrite needs to be inserted in the AC in cable and located in the screw cable cover (see picture above, left). *THE FERRITE IS REQUIRED TO MAINTAIN THE WARRANTY*.

NOTE 2: Two floating grounding cables are provided that are connected to the ground node. One cable must be connected between the to the wall frame PEM the other to the front lower cover in order to guarantee equal ground potential (see picture above, right).

2. Push the cables back through the gland plate, until sufficient cable length is left to reach the cable terminals. Ensure the PE cable is longer than the other cables.




3-Phase Connection using flexible



Conduit Installation 1.25" secured to bottom mounting area. 1-phase Version Shown

3. Slide the cable cover and tighten the two screws.

If a wired internet connection is not used, please ensure the cable entry hole is closed, to assure the IP54 grade of the cabinet, and prevent insects and small animals to enter the cabinet.



5.5 Connect cables

5.5.1 Connect PE of power cable

Preconditions:

• Tools: Wire stripper pliers; wire-end lug pliers; wire-end lug.



DANGER Hazardous voltage

Make sure that the main switch of the power supply group for the product is set to the OFF position. Perform a voltage check and make sure that the electrical power is disconnected from the system. Follow recommended *NFPA-70e* procedures.

1. Cut the PE wire of the power cable to the correct length (longer than the other phases) to reach the PE connector.



NOTICE

For safety, it is recommended that the PE wire is longer than the phase wires. This ensures the PE wire will be the last wire connected if the Terra DC Wallbox is moved by a collision.

- 2. Use wire stripper pliers to remove 0.75 (20 mm) of the insulation from the end of the PE wire and attach the cable lugs.
- 3. Pull the cover away from the connectors and remove them.
- 4. Loosen the bolts of the PE connector on the ground block.
- 5. Attach the PE wire onto the PE block.
- 6. Tighten the bolts. The advised torque value is 2 Nm.

5.5.2 Connect power cable

Preconditions:

• Tools: Wire stripper pliers; wire-end lug pliers; wire-end lugs.



DANGER Hazardous voltage Ensure the product's power supply group's main switch is set to the OFF position. Perform a voltage check and ensure the electrical power is disconnected from the system.

- 7. Cut the 3 phase wires and the neutral wire of the power cable to the correct lengths to reach the connectors.
- 8. Use wire stripper pliers to remove 0.75 in (20 mm) of the insulation from the ends of the wires insert and terminate on the appropriate terminal block
- 9. Pull the covers away from the connectors and remove them.

10.Loosen the bolts of the connectors.

- 11.Attach the four wires on to their connectors as indicated on the label on the relative terminal block (see the following picture as example).
 - From left to right for the 3-phase unit (as showed in the following picture):

N - terminal block blue, L1 - terminal block grey, L2 - terminal block grey, L3 - terminal block grey



12. Tighten the bolts. The advised torque value is 2.9Nm.

5.6 Instruction for Mounting the DC Wallbox Gun Holders

5.6.1 General

This document is intended to provide an instruction for service team / installers in order to be able to properly install the terra DC wallbox gun holders.

5.6.2 General description

The Terra DC wallbox is provided with two types of gun holders. A standard gun holder is provided with all the DC wallboxes. The standard Terra DC wallbox gun holder is illustrated in Fig.1 and Fig.2. An optional gun holder is also available as an optional / spare part and can be ordered as external kit. The optional gun holder is illustrated in Fig. 3 and 4. All the above described gun holders include adapters for CCS or Chademo charging guns.

5.6.3 Mounting instructions

The gun holders described above are intended for a very simple installation. Standard gun holder is provided with 3 holes for wall hooking while optional one is provided with a wall mounted hooking bar (10 in Fig.3) to be mounted to wall. The recommended dowels to be used are of 10 size for both cases.





Figure 1: Series production Terra DC wallbox gun holder (Chademo model).

Figure 2: Series production Terra DC wallbox gun holder (CCS model).







Figure 3: Terra DC wallbox optional gun holder.

Figure 4: Terra DC wallbox optional Gun holder; front and side view.



- 2) Fix the system on the bracket (XAP.V2M09.0)
- 3) Fix Screw on hole number 3

6 Commissioning

6.1 Commissioning preparation

Commissioning is the last phase necessary to get the Terra DC Wallbox operational. The purpose is to check the safe functioning of the charger for its operational purpose.

A certified service engineer from the ABB Service department or a trained engineer by ABB is required to perform the commissioning. During this commissioning, the safety and the functioning of the charger will be tested. ABB Form Titled "**SI-TWBCE-001 UL CSAT Procedure DC Wallbox**", (Charger System Acceptance Test) should be used for the commissioning process as it contains the checklist and contact information for activation of the charger warranty.

Before the service engineer can start, the following conditions must be met:

- All work described in Preparation, Construction and Placement and connection is complete with Power available.
- A local technician is present for assistance and to switch on the power.
- Internet access must be available in case 4G is not functional.
- A Combo compliant electric vehicle must be available for testing CCS charging.
- A CHAdeMO compliant electric vehicle must be available for testing the CHAdeMO charging.
- Any electric vehicle for instructing the site operator.



NOTICE

Warranty : It is not allowed to move the Terra DC Wallbox, after it is commissioned. In case the Terra DC Wallbox is moved without approval from ABB, the warranty will be considered void. In case of relocation please contact the local ABB Service department.

Commissioning is executed according to the CSAT checklist, this check list can be found in the Helios Suite Service tool that is available to the certified commissioning engineers or their supervising ABB organization. The following data is required for input:

- End-user Contact person (Create a contact if it doesn't exist).
- Charger address (Check the site address, it will be the address the charger was shipped to).
- Coordinates longitude and latitude for plots on the maps. If there are more chargers on 1 location, make sure the coordinates are slightly different (at least 0,0001 degrees) to prevent being displayed on the same location.
- Site name if this is useful for better recognition (example: Shell petrol station Amsterdam).
- External fuse of the charger.
- SAT (Site Acceptance Test) date.

Location remarks (any special remarks about the site, e.g. behind a gate, no photo cameras allowed etc.). Add a picture of the surrounding of the charger, upload the local CAF document A4 on the page of the charger in PDF. Change Deliver status to <SAT>.

After completing the Site Acceptance Test, ABB's Network Operation Center will be triggered to perform a final check on the connection and configuration of the charger.

Upon approval the charger will be operational and initialized for use.

7 Maintenance and Cleaning of the cabinet

7.1 Recommended Periodic maintenance

- A. Following **NFPA-70e** procedures, de-energize unit, open cover, inspect air filter, clean or replace as needed.
- B. Check input connections and terminations for proper toque values
- C. Check Grounding resistance
- D. Exercise input breaker and output DC breakers
- E. Open HMI cover, inspect capacitors and fuse connections.
- F. Clean interior with a HEPA vacuum.
- G. Blow out rear cooling fins and remove any debris
- H. Reassemble unit, energize verify input voltage, perform a charging session.
- I. Using the connected network verify charging session details.

7.2 Cleaning of the cabinet

The Terra DC Wallbox Charger is powder coated. This coating must be kept in good condition.

Clean the Terra DC Wallbox Charger three times a year in the following way:

- Remove rough dirt by spraying with low-pressure tap water.
- Apply a neutral or weak alkaline cleaning solution and let it soak.
- Remove dirt by hand with a non-woven nylon hand pad.
- Rinse thoroughly with tap water.
- Do a check on the coating and on the front cover for damage.



NOTICE

When the Terra DC Wallbox Charger is exposed to rain, it is sufficient to clean it twice a year.



CAUTION

Do not apply high-pressure water jets. Water may leak into the Terra DC Wallbox Charger. If a high-pressure water jet has been used, ensure the inside of the Terra DC Wallbox Charger is dry.

- Only use cleaning agents with a pH value between 6 and 8.
- Do not use cleaning agents with abrasive components.
- Do not use abrasive tools.

8 Technical Data

8.1 Electrical data

AC Input		
AC input voltage range	480 V _{AC} +/- 10% (60Hz)	
AC input power connection	3-phase, 480Y/277 V _{AC} : L1, L2, L3, N, GND	
Nominal input current and input power rating	32 A / 26.6 kVA at 480V, peak input current: 35 A / 26.6 kVA at 432V	
Recommended upstream overcurrent protection device rating	50 A	
Power factor	> 0.96	
Efficiency	94% at nominal output power	
DC output		
Maximum DC output power	24 kW peak; 22.5 kW continuous	
DC output voltage range	CCS1: 150 - 920 VDC CHAdeMO: 150 – 500 VDC	
Maximum DC output current	60 ADC	

General	
DC connection standard	EN61851-23 / DIN 70121 CCS 2 CHAdeMO 1.0
DC cable length	3.5 meters or 7 meters (12 feet or 23 feet)
DC plug type	CCS 1 / CHAdeMO
RFID data	ISO/IEC14443A/B, ISO/IEC15693, NFC rea- der mode, Mifare, Calypso
RFID system	FeliCa™1, NFC reader mode
Network connection	GSM / 4G modem 10/100 Base-T Ethernet

8.2 Mechanical data

Mechanical data	
Dimensions (H x W x D)	770 mm x 585 mm x 300 mm / 30.32" x 23.03" x 11.81"
Weight	70 kg / 154.32lbs
Volume	0,135 m ³
Dimensions including packaging (H X W x D)	650 mm x 1200 mm x 800 mm /25.6" x 47.25" x 31.5"
Weight including packaging	80 kg / 176.37 lbs.
Mechanical impact protection	IK10

8.3 Environment

Environmental data	
Ingression protection	IP54, NEMA 3S; indoor and outdoor
Temperature range – Operation	-35°C to + 55°C /-31F to + 131F (derating applies between 45°C and 55°C / 113F-131F)
Temperature range - Storage	-40 °C to +70 °C / -40F to +158F
Humidity	20% - 95% RH - non-condensing
Operational noise level	55 dBA @25°C
Altitude	2500 m max.

8.4 Certifications

EMC: EN 61000-6-4 Class A emission; EN 61000-6-3 Class B emission; EN 61000-6-2 immunity.
 LVD: IEC 61851-23, IEC 61851-1, IEC 62196, IEC 60950, EN 61010, EN 60335 (see certificates)
 RFID: ETSI EN 300 330

- UL 2202
- CSA STD C22.2 No. 107.1
- FCC Part 15 Class A

9 Contact information



NOTICE In case of problems Please contact your local ABB Service organization or Service partner for first line problem analysis and solving. In case they cannot solve the problem, they will contact the second line Service organization.

ABB in your country

Please contact ABB in your country for sales, delivery and service information.

ABB EV Infrastructure USA

ABB Inc. 950 E Elliott Rd Tempe, AZ 85284 Suite 100 United States Phone: 800-435-7365 E-mail: US-evci@us.abb.com

ABB EV Infrastructure Canada


ABB Inc. 800 Hymus Boulevard Saint-Laurent, QC H4S 0B5 Canada Phone: 800-435-7365 E-mail: CA-evci@abb.com

ABB EV Infrastructure Global

- Address Heertjeslaan 6 2629 JG, Delft The Netherlands
- Telephone +31 70 307 62 00
- Mail info.evi@nl.abb.com

10 Appendix A – Mounting points

10.1 Terra DC Wallbox Charger wall mounting



11 **Appendix B - Disposal instruction**

Directive on Waste Electrical and Electronic Equipment (WEEE -11.1 2012/19/EU)

ESPAÑOL

X

X

Ø

ny i Elektroniczny podlegający rce zgodnie z Dyrektywą (WEEE

PORTUGUÊS

ABB

ENGLISH

ent (WEEE

X

FRANCAIS

roduct shall not be mixed or dispo-shold waste, at their end of use. This product shall be handed over to your local com-munity waste collection point for the recycling of the

ve aux déchets d'équipements rominues (WEEE - 2012/19/EU) ctriques et Ce symbole (poubelle interdite) apposé sur le produit indique qu'en fin de vie ce produit ne doit pas être traité avec les déchets ménagers. Il doit être remis à un point de collecte approprié pour le recyclage des appareils électriques et électroniques.

And use puis amples informations, veuliez contacter le service de callecte des déchés ménagers local. Service de callecte des déchés ménagers local. Service de callecte des déchés ménagers local. Ce produit contient des dés antes ménagers local. Service de callecte des déchés ménagers local. Ce produit contient des dés ménagers local. Service de callecte des déchés ménagers local. Ce produit contient des dés ménagers local. Service de callecte des déchés ménagers local. Ce produit contient des dés ménagers local. Service de callecte des déchés ménagers local. Service de callecte de produit yous con-calion in the correct disposai d'inis product, you Inibuenze à assure le traitement, la récupération et le nour environment will be protected.

sobre residuos de aparat cos (WEEE - 2012/19/EU)

achada) no deben eliminarse con cos una vez finalizada su vida útil. Este producto debe entregarse a un punto de gida de la comunidad local para su recupera reciclado.

Para mayor in El manejo ina

NEDERLASNDS

X

trische en elek nderliik innezano van de Richtlijn betreff

Het symbool (doorgekruisde afvalbak het product geeft aan dat het product van haar levensduur niet samen met of huishoudafval mag worden weggegooi

Het product moet naar depot) worden gebracht worden gerecycled.

eem voor meer inforn

Het kan nadelig

DANSK

X

X

X

SUOMI

isk og el risk og elektror X

X

Produktet skal aflev

takt w bortskaffelse af affald kan h

et og fi

X

zu

X

Směrni (WEEE

se po ukončeni wat společně s

určené sběrné

X

es elektronikus beren-ló (WEEE - 2012/19/EU) kell gyűlteni

szimbólum (keres 7y a terméket has:

t újbóli hasznosításra le kell adnia a kije últó hahar:

ájárul annak újrafelhasználá oz és visszanverésébez és

ért kérjük, fordulion az országában ulladékkezelésnek potenciálisan ve-miatt negatív hatása lehet a kömye-1 egészsécm ITALIANO

DEUTSCH

ČESKY

Elektrick

MAGYAR

ng mit der Richtlinie über nik-Altgeräte (WEEE - 2012/19/ di race sui Ri

ne) auf dem Pro-

iler Haushaltsabfall in den Müll gege-fen, sondern zum Recvcling an einer stelle abzuge

ormationen wenden Sie sich bitte an die ung zuständigen örtlichen Behörden. näßer Entsorgung besteht das Risiko uswirkungen auf Umwelt und Gesungefährliche Substanzen. Durch ordnungsgemäßen Entsorgung derverwendung, das Posseling

že výrobek ichat a vyhazi

je třeba odložit na

iata in conformità alla Direttiva cchiature Elettriche ed Elettro-

dotto non deve essere alla fine della sua vita.

ersi all'organo statale Per ulte itimento dei rifiuti nel proprio pa Uno smaltimento dei rifiuti inappropriato può avere effetti negativi sull'ambiente e sulla salute umana a causa di sostanze potenzialmente pericolose. Collabo-rando allo smaltimento corretto di questo prodotto, si

Equipamentos Eléctricos e Ele dos seletivamente de acordo o lativa aos resíduos de equipar eletrónicos (WEEE - 2012/19/EU) O símbolo (caixote de lixo de rodas

izada) em seu produto indica que o pro sua vida útil, não deve ser misturado o n o lixo doméstico comum. Este produto deverá ser entregue a

O trata

SLOVENŠČINA

Električna in elektronska oprema s v skladu z Direktivo o odpadni tektronski opremi (WEEE - 2012/19

omo z produkturka wody, ka ma produktu u suka ka se je za zicelika po končani i tek se se je zicelika po končani i se se je za zicelika je zicelika je za zicelika je za

SVENSKA

X

Elektriska och elektroniska in separat i enlighet med di utgörs av eller innehåller ele utrustning (WEEE - 2012/19) WEEE - 2 Denna symbol (en överkorsad sopt innebär att produkten ej ska blanda ditt hushållsavfall när den är förbru

Pyydä lisätietoja jät Tämän tuotteen asi stamisella autotaan

Olämplig avfallshante miljön och på mänsk nehålla farliga ämnen Vi ber om ditt samar produkt för att bidra

ooskõlas elektri- ja e iga (WEEE - 2012/19/F

n ja terveyteen voi aiheutua mu epäasianmukais

osoittaa, että tuotetta ei lousiätteiden koncon

Tuote on luc

X

SRPSKI

piti zasebno i električnoj i e

na vašem isteku svog radnog veka ne sme j zajedno sa otpadom iz domaćinstv Ovaj proizvod se mora predati na mo otpada za reciklažu u vašoj lokalnoj

Za dodatne informacije m organ za odlaganje otpada

Nepravilno rukovanje otpadom može utiče na životnu sredinu i zdravlini livući

spodarka Odp kládání s odpady by mohlo mít za násle-vliv na životní prostředí a lidské zdraví žného vzniku škodlivých látek. Pomocí

POLSKI

Sprzet Ele

selektywnej z 2012/19/EU

Ina obspolanit Oppolanit w Tream (a characteria) Niewtaści we manipulowanie oddani może negatyw-nie oddziaływać na środowsko i zdrowie ludzi, wsku-tek potencjanych substanji niebezpiecznych. Współ-przując przy prawidlowym usunięciu tego produktu, przyczyniasz się do ponownego użyda, recyklingu i odzysku produktu i w ten sposó nasze środowisko.

Produkt ten powinien zostać dostarczony do lokalnego komunalnego punktu zbiórki odpadów, w celu recyklin-

adami w Twoim kraju.

X SLOVENČINA

výrobku končení bežným

tu vo vašei

LIETUVIŲ

Zaradi nevarnih snovi ima lahko napačno upravljanje z

ota jūsų vietos ntrui, kad būtų pa-

šalies acijos galite

LATVIEŠU

ko un

tiks nodots vietējā l

X

Imajanusse puduvarate regulasikonturgui. Käesoleva toote vale käsittemine selle kõrvald võib põhjustada võimalikest riskiainetest tui negatiivset mõju nii keskkonnale kui ka Teiet te. Toote korrekine käsitsemine ka peale selle tuskõltmatuks muutumist ja Teie kaasabi käs toote korduvkasutusse või ümbertöötusesse s pri pravilnem

X

ktrični in

EESTI

eraldi ko

X

Ta izdelek je potrebno oddati vaši lokalni deponiji z Käesolev toode on ümbertöödeldav ning tuleb viia ko-odpadki za predelavo takšnih izdelkov. halikku prügikogumis- või ümbertöötlemiskeskusesse.

Za podrobnejše podatke se obmite na državni urad za odstranjevanje odpadkov v vaši državi. selle riiglasutuse poole Tele riigis, mis tegeleb průgi-majadrúnese nu huteni remulatsionnídna

mbertöötlusesse kaitsta ühist loo

X

ΕΛΛΗΝΙΚΆ

12 Appendix C – Pedestal requirements

Any pedestal solution designed for Terra DC Wallbox needs to fulfill the specific ISO standards for civil constructions (note: specific local regulations may apply).

Additionally, whereas no specific constraint is provided by local regulations, the minimum set of requirements necessary to provide a safe installation are listed in the table below to be verified in the temperature range between -50° C - $+60^{\circ}$ C:

Minimum Wind load resistance	100km/h
Minimum compression load capability (applied on center of mass of the WB)	4kN
Side / Back / frontal impact MAX (applied on the pedestal/WB) higher point	3kN
Pulling /Pushing force applied (to gun holders if they are mechani- cally connected to same structure and external to the WB area)	3kN
Min / Max distance of gun holder from WB (if mechanically con- nected to pedestal structure)	300mm / 1000mm
Rust protection paint	Yes
Minimum clearance areas side / top / bottom around the charger	300mm
Recommended foundation requirements (min tilting torque)	To be designed con- sidering the max loads in each direc- tion
Vibration test required on the full system	According to proce- dure described in IEC 60068-2-27: 2008 and IEC 60068-2-6: 2007
Electrical ground connection	To the chassis of the DCWB